
ROUGH TERRAIN CRANE

TR-200M

JAPANESE SPECIFICATIONS

OUTLINE	SPEC. NO.
4-section Boom, 1-stage Jib	TR-200M-2-00102

Control No. JA-02



TR-200M

CRANE SPECIFICATIONS

CRANE CAPACITY

8.35m Boom 20,000kg at 3.5m (7 part-line) 14.3m 16,000kg at 3.5m (6 part-line) Boom 20.25m Boom 9,000kg at 6.0m 4 part-line) 26.2m Boom 6,800kg at 7.0m 4 part-line) 3,000kg at 72° 7.0m Jib 1 part-line) Single top 3,000kg 1 part-line)

MAX. LIFTING HEIGHT

Boom 26.5m lib 34 0m

MAX. WORKING RADIUS

Boom 24.0m Jib 27.5m

BOOM LENGTH

8.35m - 26.2m

BOOM EXTENSION

BOOM EXTENSION SPEED

17.85m / 76s

JIB LENGTH

MAIN WINCH SINGLE LINE SPEED

High range: 103m/min (4th layer) Low range: 51.5m/min (4th layer)

MAIN WINCH HOOK SPEED High range:

14.7m/min (7 part-line) 7.3m/min (7 part-line) Low range:

AUXILIARY WINCH SINGLE LINE SPEED

88m/min (2th layer)

AUXILIARY WINCH HOOK SPEED 88m/min

(1 part-line) **BOOM ELEVATION ANGLE**

0° - 80°

BOOM ELEVATION SPEED

 $0^{\circ} - 80^{\circ} / 40s$

SWING ANGLE

360° continue

SWING SPEED

3.0rpm

WIRE ROPE

Main Winch

16mm × 150m (Diameter×Length) 7×7+6×Fi(29) Calss B ordinary · Z twist Spin-resistant wire rope

Breaking strength 17.6t

Auxiliary Winch

16mm × 75m (Diameter×Length)

7×7+6×Fi(29) Class B ordinary Z twist

Spin-resistant wire rope Breaking strength 17.6t

4-section hydraulically telescoping boom of box construction.

(stage 2: sequential; stages 3, 4: synchronized)

BOOM EXTENSION

2 double-acting hydraulic cylinder 1 wire rope type telescoping device

1-staged swingaround boom extension which stores

alongside boom base section.

Offset (10°)

SINGLE TOP

Single sheave. Mounted to main boom head for single line work.

Driven by hydraulic motor and via spur gear speed reducer.

Power load lowering / free-fall lowering type

2 single winches

BOOM ELEVATION

1 double-acting hydraulic cylinders

SWING

Hydraulic motor driven planetary gear reducer

Swing bearing

Swing free/lock changeover type

Hand brake

OUTRIGGERS

Fully hydraulic X-type (floats mounted integrally)

Slides and jacks each provided with independent operation

device

Full extended width Middle extended width

3.6m

MAX. OUTRIGGER LOAD

HYDRAULIC PUMPS

3 gear pumps

HYDRAULIC OIL TANK CAPACITY

370 liters

SAFETY DEVICES

Automatic moment limiter (AML-U)

Over-winding cutout

Level gauge

Hook safety latch

Winch drum lock Hydraulic safety valve

Telescopic counterbalance valve

Elevation counterbalance valve

Jack pilot check valve

Swing lock

EQUIPMENTS

Crane cab heater (with defroster)

Reclining seat (with headrest)

CARRIER SPECIFICATIONS

ENGINE

Model HINO EL100

Type 4-cycle, 6-cylinder, direct-injection, water-cooled

diesel engine

Piston displacement 7,862cc

Max. output Max. torque 165PS at 2,800rpm 49kg·m at 1,600rpm

TORQUE CONVERTER 4-element, 1-stage unit

TRANSMISSION

Power shift type (wet multi-plate clutch)

3 forward and 1 reverse speeds

REDUCER

Axle dual-ratio reduction

DRIVE

2-wheel drive (4×2) / 4-wheel drive (4×4) selection

FRONT AXLE

Full floating type

REAR AXLE

Full floating type (with no-spin differential)

SUSPENSION

Front Parallel leaf spring type Rear Parallel leaf spring type

STEERING

Fully hydraulic power steering

BRAKE SYSTEM

Service Brake

Hydraulic brake with pneumatic power device.

Internal expanding leading and trailing type

Parking Brake

Mechanically operated, internal expanding duo-servo shoe type acting on drum at transmission case rear.

FRAME

Welded box-shaped structure

ELECTRIC SYSTEM

24 V DC. 2 batteries of 12V (120Ah)

FUEL TANK CAPACITY

250 liters

CAB

Two-man type

TIRES

Front 14.00-24-20PR (OR)

Rear 14.00-24-20PR (OR)

SAFETY DEVICES

Emergency steering device

Spring lock device

GENERAL DATA

DIMENSIONS

 Overall length
 10,450mm

 Overall width
 2,490mm

 Overall height
 3,420mm

 Wheel base
 3,000mm

 Tread
 Front
 2,060mm

 Rear
 2,060mm

WEIGHTS

Gross vehicle weight

Total 22,710kg
Front 11,355kg
Rear 11,355kg

PERFORMANCE

Max. traveling speed 40km/h Gradeability (tan θ) 0.6

Min. turning radius 4.9m (4-wheel steering) 8.3m (2-wheel steering)

TOTAL RATED LOADS

(1) With outriggers set (360°)

Unit: ton

	Outriggers fully extended						Outrig	gers m	iddle e	extend	ed
B A (m)	8.35 m	14.3 m	20.25m	26.2 m	E C	7.0 m	B A (m)	8.35 m	14.3 m	20.25m	26.2 m
3.0	20.0	16.0			80	3.0	3.0	18.0	16.0		
3.5	20. 0	16.0	9.0		75	3.0	3.5	15.0	16.0	9.0	
4.0	18.5	15.5	9.0	1	72	3.0	4.0	13.0	13.5	9.0	
4.5	16.5	14.2	9.0	6.8	70	2.8	4.5	11.0	11.0	9.0	6.8
5.0	15.0	13.1	9.0	6.8	65	2.4	5.0	9.0	9.0	9.0	6.8
5.5	13.7	12.1	9. 0	6.8	60	2.0	5.5	7. 7	7. 55	8.0	6.8
6.0	1 2. 5	11.2	9.0	6.8	55	1.65	6.0	6.6	6.4	6.8	6.8
6.5	11.5	10.4	8.5	6.8	50	1.3	6.5	5.7	5.5	5.9	6.2
7. 0		9.7	8.0	6.8	4.5	1.0	7. 0		4.8	5.2	5.4
8.0	·	7.8	7. 1	6.1	40	0.8	8.0		3.7	4.1	4.3
9. 0		6.2	6.3	5.5	35	0.65	9.0		2.9	3.3	3.5
1 0. 0		5.0	5.4	4.9	30	0.5	10.0		2.3	2.7	2.9
11.0		4.15	4.6	4.4			11.0		1.85	2.2	2.45
12.0		3.5	3.9	4.0			12.0		1.5	1.85	2.1
13.0			3.35	3.55			13.0			1.55	1.75
14.0			2.9	3.1			14.0			1.3	1.5
15.0			2.55	2.7			15.0			1.05	1.25
16.0			2.2	2.4		,	16.0			0.9	1.05
17.0			1.95	2.1		·	17.0			0.7	0. 9
18.0			1.7	1.85			18.0			0.5	0.7
19.0				1.65			19.0			-	0.6
20.0				1.45		,				·	
22.0				1.15	A = Boo	m length	$\mathbf{B} = \mathbf{Wor}$	rking ra	dius C	z = Jib	length

A = Boom length B = Working radius C = Jib length

E = Boom angle

NOTES:

24.0

- 1. The total rated loads shown are for the case when the outriggers are set horizontally on firm ground. The values above the bold lines are based on the crane strength while those below are based on the crane stability.
- 2. The weights of the slings and hooks (main winch hook: 230kg, auxiliary winch hook: 50kg) are included in the total rated loads shown.
- 3. The total rated load is based on the actual working radius including the deflection of the boom.
- 4. The number of part lines for each boom length should not exceed the values below. The load per line should not exceed 2.9t for the main winch and 3.0t for the auxiliary winch.

Α	8.35 m	14.3 m	20.25 m	26.2 m	J
H	7	6	4	4	1

A = Boom length H = No. of part-line J = Jib / Single top

- 5. The total rated loads for free-fall operations is 1/5 of the total rated loads given above. The load per line in this case should not exceed 0.6t for both the main winch and the auxiliary winch.
- 6. Do not use the jib with the "Outriggers middle extended"
- 7. The total rated load for the single top shall be the value obtained by subtracting 150kg from the total rated load of the main boom and must not exceed 3.0t.

(2) Without outriggers

Unit: ton

В	· · ·		Statio	nary		Creep (travelling at 1.6km/h or less)						
B	8.35 m BOOM		14.3 m BOOM		20.25 mBOOM		8.35 m BOOM				20.25 m BOOM	
(m)	F_	G	F	G	F	G	F	G	_ F _	G	F	G
3.0	1 2. 0	8.0	8.5	7. 0			8.5	6.0	6.5	4.8		
3.5	1 0. 5	7. 1	8.5	7. 0	6.0	4.5	7. 7	5.0	6.5	4.8	5.0	3.2
4.0	9.4	5.8	8.5	5.5	6.0	4.5	6.9	4.3	6.5	4.1	5.0	3.2
4.5	8.4	4.7	7.8	4.4	6.0	4.5	6.2	3.6	6.0	3.4	5.0	3.2
5.0	7. 6	3.9	7. 0	3.6	6.0	4.0	5.55	3.0	5.3	2.8	5.0	3.2
5.5	6.6	3.2	6.2	3.05	5.5	3.4	5.0	2.5	4.75	2.3	4.7	2.7
6.0	5.8	2.7	5.4	2.55	5.1	2.9	4.5	2.05	4.3	1.9	4.3	2.3
6.5	5.0	2.3	4.65	2.15	4.65	2.5	4.0	1.7	3.9	1.6	3.9	2.0
7. 0			4.1	1.8	4.3	2.15	:		3.5	1.35	3.6	1.7
8.0			3.2	1.3	3.55	1.6			2.7	0.95	3.0	1.25
9.0			2.55	0.9	2.9	1.2	:		2.1	0.6	2.4	0.9
10.0			2.05	0.55	2.4	0.9	-		1.65		1.95	0.7
11.0			1.6		2.0	0.65			1.3		1.6	
12.0			1.25		1.6				1.0		1.3	
13.0					1.3						1.05	
14.0					1.1						0.9	
15.0					0.9						0.7	
16.0					0.75		-				0.55	
17.0			1		0.6		1					


 $B = Working radius F = Front G = 360^{\circ}$

NOTES:

- The total rated loads shown are for the case when the crane is set horizontally on firm ground. The values above the bold lines are based on the crane strength while those below are based on the crane stability. The foundation, working conditions, etc. should be taken into consideration adequately when using the crane for actual work. (Tire air pressure: 8.0kg/cm²).
- 2. The weights of the slings and hooks (main winch hook: 230kg) are included in the total rated loads shown.
- 3. The total rated loads are based on the actual working radii into which are included the deflections of the boom and the tires.
- 4. The number of part lines for each boom length should not exceed the values below. The load per line should not exceed 2.9t (for the main winch).


Α	8.35 m	14.3 m	20.25 m	A = Boom length
н	7	c	4	H = No. of part-line

- 5. Free-fall operations should not be performed without outriggers.
- 6. The 26.2m boom, the jib and the single top should not be used without the outriggers.
- The boom must be kept inside a 2° area (1° each to the left and right) over front of the carrier when performing "Over front" crane operations without the outriggers.



- 8. When creeping while hoisting a load, the swing brake should be applied, the load should be kept as close to the ground as possible but not touching the ground and the speed should be kept at 1.6km/h or less. In particular, any abrupt steering, starting or braking must be avoided.
- 9. Crane operations should not be performed when creeping while hoisting a load.


WORKING RADIUS - LIFTING HEIGHT



WORKING RADIUS (m)

NOTES

- 1. The deflection of the boom is not incorporated in the figure above.
- 2. The figure above is for the case when the outriggers are fully extended (360°).





					·
•					
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~					
	,				
		·		·	
ta di salah sa					
		·		·	
•		:			
				·	
		•	•		
				<del>-</del>	
					<del></del>
			•		
			<del></del>		
			,		
			·		
			· 		
		<del></del>	f		
				*	
···					
	·				

## **ROUGH TERRAIN CRANE**

**TR-200M** 

**Optional Jib** 

JAPANESE SPECIFICATIONS

These specifications are for the optional jib for the TR-200M type crane.

Refer to these specifications along with specification sheet no. TR-200M-2-00102.

Control No. TR-200M-2-TJ-01

#### **TR-200M**

CRANE SPECIFICATIONS

**Optional Jib** 

JIB

1-staged swingaround boom extension which stores alongside boom base section. Dual offset (10°, 30°) type. With jib extending device

#### **BOOM LENGTH**

7.0m

MAXIMUM TOTAL RATED LOAD

3,000kg

(1 part-line)

MAX. LIFTING HEIGHT

34.0m

MAX. WORKING RADIUS

27.8m

## TOTAL RATED LOADS

**Optional Jib** 

Unit: ton

Outriggers	Outriggers fully extended (360°)									
E(°) D	10°	30°								
80	3.0	2.0								
75	3.0	2.0								
73	3.0	2.0								
70	2.75	2.0								
65	2.35	1.85								
60	2.0	1.7								
55	1.65	1.45								
50	1.25	1.15								
45	0.95	0.9								
40	0.75	0.7								
35	0.6	0.5								
30	0.45	0.4								

D = Jib offset


E = Boom angle

#### **NOTES:**

- 1. The total rated loads shown are for the case when the outriggers are set horizontally on firm ground. The values above the bold lines are based on the crane strength while those below are based on the crane stability.
- 2. The weights of the slings and hooks (auxiliary winch: 50kg) are included in the total rated loads shown.
- 3. The number of part lines for the hook is 1.
- 4. The total rated loads for free-fall operations is 1/5 of the total rated loads given above.

# LIFTING HEIGHT (m)

## **WORKING RADIUS - LIFTING HEIGHT**



WORKING RADIUS (m)

#### **NOTES:**

- 1. The deflection of the boom is not incorporated in the figure above.
- 2. The figure above is for the case when the outriggers are fully extended (360°).



				·
				<del></del>
~			* <b>-</b>	***************************************
		1		
		<del></del>		
	[			
		<del>}</del>		
	· 			***************************************
•	. *		. *	
		- <b></b> - <u>-</u>		
	t e	į		
	!			
	!, 			
·				
		•		
		i		
			·	
		<del>-</del>		<del></del>
		:		